



# Assembly of Modular Components into Credenza Shell


## Recommended Tools




## Hardware Used



## Modular Credenza Shell




## Pedestals without Backs




## Step 1 Leveling Shell

- Adjust the leveling guides to level the credenza shell in place.
- diagram 1*




## Step 2 Assembly of the Shell

- Access will be needed to the interior cabinet. Carefully remove any drawers from modular units.
- diagram 2*
- Slide the modular cabinets into place according to the plan. Level the modular units accordingly, making sure the credenza shell is still leveled properly and all of the glides on the credenza shell still make contact to the floor.
- diagram 3*
- Position the remaining modular units into the shell as per the plan. Level the additional units repeating the above steps. The configuration of modular units into credenza shell does not allow the credenza shell to be completely filled with modular units.



*note: keep drawers in the correct order, each drawer has been fitted to a particular location in the modular unit.*




**Notice To Installers:** Failure to comply with installation instructions will compromise the safety, durability and performance of this product, which may risk injury to the user of this product and/or diminish the product life cycle. Jasper Group assumes no liability in these instances.



## Assembly of Modular Components into Credenza Shell *(continued)*

### Step 3 Attaching Modular Units


- Use the provided hardware (#8 x 1<sup>1</sup>/<sub>2</sub>" Pan Head Wood Screws) to secure top of modular unit to underside of the credenza shell top.  
*diagram 4*
- Use the provided hardware (#12 x 3/4" Pan Head Wood Screws) to secure the modular unit to the interior back using the attached "L" brackets  
*diagram 5*
- Make sure the unit is still level with all glides touching the floor.
- If applicable put the drawers back into the pedestal, make sure drawers are installed in the correct order.  
*diagram 6*



*diagram 4*



*diagram 5*



*diagram 6*

**Notice To Installers:** Failure to comply with installation instructions will compromise the safety, durability and performance of this product, which may risk injury to the user of this product and/or diminish the product life cycle. Jasper Group assumes no liability in these instances.